

## BOQ-1

Name of work : Emergency repairing of damaged tower at loc- 48 of 132kV Capital-Narengi-CTPS-Sonapur DC TL behind Narengi Samshan at Bonda.

Name of Bidder:

Sl. No.	Description of item	Unit	Qty	Rate(in Rs.)	Amount(in Rs.)
1	Fabrication, Repairing & Replacement of damaged tower members (48 nos of members of assorted size)	per MT	2.5		
2	Replacement of damaged tower legs including all necessary civil works	per Leg	4.0		
3	Dismantling of damaged tower legs, tower members and transporting to Kahilipara Store	per MT	2.5		
4	Painting of tower with bituminous paint of approved quality upto 3 mtrs from ground level including cost of paint	per tower	1.0		
5	Earthing work (including supply of all materials)	per tower	1.0		
6	PCC work upto 3 m from ground level (leg and additional 2 nos bracing pieces per leg)	per leg	12.0		
7	Head loading of tower materials for hilly areas (beyond 10 mtrs)	MT/m	8.00		
8	Welding of nuts and bolt	per tower	1.00		
				<b>Total=</b>	
				<b>GST @ 18% =</b>	
				<b>Grand Total =</b>	
				<b>Say =</b>	

## BOQ-2

Name of work: Emergency repairing of damaged tower at loc- 60,61 of 132kV Capital-Narengi-CTPS-Sonapur DC TL in Panikhaiti Area

Name of Bidder:

Sl. No.	Description of item	Unit	Qty	Rate(in Rs.)	Amount(in Rs.)
1	Fabrication, Repairing & Replacement of damaged tower members (i.e. loc 60--20 nos of members of assorted size + loc 61-- 20 nos of members of assorted size i.e. 40 nos of members assorted size)	per MT	2.0		
2	Replacement of damaged tower legs including all necessary civil works (i.e. loc 60--4 no of legs loc 61-- 2 nos of legs)	per Leg	6.0		
3	Dismantling of damaged tower legs, tower members and transporting to Kahilipara Store	per MT	2.0		
4	Painting of tower with bituminous paint of approved quality upto 3 mtrs from ground level including cost of paint	per tower	2.0		
5	Earthing work (including supply of all materials)	per tower	2.0		
6	Head loading of tower materials for hilly areas (beyond 10 mtrs)	MT/m	4.0		
7	PCC work upto 3 m from ground level (leg and additional 2 nos bracing pieces per leg)	per leg	14.0		
				<b>Total=</b>	
				<b>GST @ 18% =</b>	
				<b>Grand Total =</b>	
				<b>Say =</b>	

## Summary

Sl no.	BOQ/ Price Schedule	Description of work	Quoted amount (incl. GST)
1	BOQ-1	Emergency repairing of damaged tower at loc- 48 of 132kV Capital-Narengi-CTPS-Sonapur DC TL behind Narengi Samshan at Bonda.	
2	BOQ-2	Emergency repairing of damaged tower at loc- 60,61 of 132kV Capital-Narengi-CTPS-Sonapur DC TL in Panikhaiti Area	
		<b>Grand Total (1 + 2) =</b>	

*Name and signature of bidder:*