

**BOQ**

Name of work: Temporary protection work at location no: 136 of 132kV  
S/C Dibrugarh-Tinsukia line to be carried out near the bank of Sessa river to avoid collapse of tower due to erosion.

Name of the firm :

Sl no.	Particulars	Unit	Qty	Rate (Rs.)	Amount(Rs.)
1	Supply of Geotextile bag				
	(i) Geotextile Bag, Type A (1.03m x 0.70 m)	No	500		
	(i) Geotextile Bag, Type C (1.50m x 1.00 m)	No	120		
2	Supply of river silt for filling of Geotextile bags	Cum	70		
3	Supply of Sweing thread/Yam PPMF Stitching Thread	No	620		
4	Engagement of skilled labours for excavation and levelling of erosion site where geobags are to be stacked	Mandays	64		
5	Engagement of skilled labours for filling of Geobags type-A of size 1.03m x 0.70m	Mandays	70		
6	Engagement of skilled labours for filling of Geobags type-C of size 1.5m x 1.0 m	Mandays	52		
7	Engagement of skilled labours for preparation of Geobags palisade	Mandays	90		
	Total amount (Rs.)				
	Add GST				
	Grand Total (Rs.)				