

BOQ

Name of work:

Name and Address of the Bidder:

Sl.No.	Item Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Supply of 415 volt ,500A, 3-Ph cubical type indoor floor mounted ACDB, as per specification comprising of two sections, each section will fed from independent auxiliary Transformers Bus-bar rating 600A,25 KA for 1 sec,Cu,IP54,2mm cold rolled/3mm hot rolled- 1.1) 500Amps TPN MCCB for incomer feeder=2 Nos (Microprocessor based) 1.2)500Amps TPN MCCB for Bus coupler=1 Nos (Microprocessor based) 1.3)100Amps TPN MCCB for outgoing feeder=3 Nos (Microprocessor based) 1.4)63Amps TPN MCCB for Outgoin feeder=6 Nos 1.5)32Amps TPN MCCB for Outgoin feeder=6 Nos 1.6)16A SP MCCB for outgoing feeder=10 Nos 1.7)10A SP MCCB for outgoin feeder =8 Nos	1	No		
2	F&I charge for Item Sl. No.1	1	No		
3	Erection, Testing & comissioning for Item Sl. No. 1	1	Job		
Total=					
Adding GST @18%=					
Grand Total =					
Say=					