

BOQ

Name of work: Part C - Conductor shifting including carriage of T&P materials, re-stringing of line and dismantling of existing (A+0) 220 kV D/C Towers for 220 kV Mirza-Boko T.L.(Single Circuit) related to LILO line for 220kV/33kV GIS,Chaygaon, AEGCL at IGC, Chatabari Campus.

Name and Address of Bidder:

Sl.No	Particulars of Job	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Dismantling of conductors (3 nos.) from ERS tower	2	Job		
2	Opening and lowering of conductor including all hardware from existing tower locations (Loc-235 (B+0) to Loc-247 (B+3)). Total D/C span length 3.832km=22.992KM	11.496	per km/per conductor		
3	Stringing of Conductor(6 nos) from ERS tower to newly erected towers at Loc no 337(D+3) and Loc 338(B+0) and restringing work(Loc-235 (B+0) to Loc-247 (B+3) at Jambari, Chaygaon.	11.496	CKM		
4	Dismantling of complete tower and transportation including all hardware fittings to Sarusajai GSS ,and stacking at TSD Sarusajai store (2 nos 220 KV Tower).	9	Per MT		
5	Jumpering work	12	Job		
6	Additional unskilled labour charges as night chowkider and for material headloading, conductor laying, etc	50	Nos		
7	Additional skilled labour charges for tower inspection, insulator hoisting, conductor laying, cutting, hardware fittings, etc for stringing works	50	Nos		
8	Temporary bamboos scaffolding for road crossing in between loc No.236 (A+0) and 237(A+0)	1	L/S		
				Sub-total =	
				GST @ 18% =	
				Total =	
				Say =	