

**PRICE BID**

**Name of Work: Construction of an Open Shed with chain link boundary fencing for Transformer Oil Drums at 132kV Dhemaji GSS.**

**NIT No. AEGCL/DGM/TTC/NLP/T-3/2025-26/ 67**

Sl No	Item Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	0.11138	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	15.4290	Cum		
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	145.13	Kg		
4	Providing soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete. (c) Stone soling of thickness 150mm	3000.00	Sqm		
5	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	4.752	sqm		
6	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in- charge. Made of G.I. wire of dia 4 mm	83.62	Sqm		

SUB TOTAL =

Add 18% GST =

Grand Total =

Say =

In words: