

BOQ**Name of Work:- Repairing and renovation of Quarter no RCC Type III/2 Unit 1 at Sarusajai AEGCL Colony****Name & Address of Bidder:**

Sl. No.	Description of Item	Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	370.00	sqm		
2	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	320.00	sqm		
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work Asian paints/berger	370.00	sqm		
4	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm)	180.00	sqm		
5	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	22	each		
6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Concealed work, including cutting chases and making good the walls etc.				
	25 mm nominal dia Pipes	10.00	rm		
7	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5 mm or 35x 5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge.	167.52	kg		
Total=					
Adding 18% GST=					
Grand Total=					
Say=					