

**Financial Bid**

**Name of Work:- Renovation and repairing works of proposed AGM, Nagaon T&T Division office at 220KV Samaguri GSS Campus, AEGCL.**

**Bidder's name:**

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Demolishing the plastering from walls/ R.C.C. and P.C.C. members without causing any damage to the wall/ member upto any height including disposal of debris as directed for all levels.	0.79	Cum		
2	Demolishing CC floors of various thickness including top layer and base course and disposal of debris as directed for all levels.	45.00	Sqm		
3	Dismantling and removing the existing door and window frame (chowkath) both wooden and steel of different sizes without damaging the walls and removing the frame and necessary repairs to the edges of the walls as directed for all levels. (i) Area of door/window up to 3.00 m2 Doors	2	each		
	(i) Area of door/window above 3.00 m2 windows	3	Each		
4	Dismantling all types of corrugated/ trapezoidal sheet roofing including ridges, hips, valleys and gutters etc. and stacking the materials as directed by the department for all levels	32.04	Sqm		
6	40 mm thick cement concrete floor consisting of 25 mm under layer of cement concrete in prop. 1:3:6 (1cement : 3 coarse sand : 6 coarse aggregate of 12.5 mm and down) and 15 mm thick wearing layer in cement concrete in prop. 1:1:2 (1cement :1 coarse sand : 2 coarse aggregate of size 10mm down) finished with a floating coat of neat cement finish using cement slurry for bond @ 2.75 kg. per square metre of floor area , wearing layer is to be laid in panels including curing etc. complete as directed.	45.00	Sqm		
7	Providing corrugated Galvanized Iron Sheet roofing of TAIA SHAKTEE/SAIL/JSW Steel including fitting and fixing necessary galvenised J or L hooks, bolts and nuts 8 mm dia with bitumen washer 25mm dia x 3 mm thick and 1.6 mm thick limpet washer complete excluding cost of roof truss, purlin etc. (Roof trusses and purlin etc. to be measured and paid separatelv). (iii) 0.60 mm thick	32.04	SQm		
	Providing wood work in frame (chowk aths) of doors, windows, clerestory windows and other similar works wrought. framed and fixed in position in contact with C.C or				

9	roughly framed and fixed in position in contact with side of brick masonry wall including supplying, fitting and fixing with M.S. hold fast (40mmx3mmx250mm) as per design embedded in cement concrete block in proportion 1:2:4 and with two coats of kiricide oiling to the timber faces in contact with C.C and masonry as directed and specified (b) With 1st Class timber (Bonsum/ Sundi)	0.25	Cum		
10	Providing, fitting and fixing factory made wooden panelled doors with panel inserts of 75mm to 50mm width and 12mm to 20mm thickness, joined together with continuous tongue and groove joints glued together with Movicol or other approved adhesive leaving a vertical groove of 7.5mm to 15mm between the inserts, the edges of panel inserts being feather tongue into styles and rails including providing three pairs of oxidised M.S butt hinges (100mm x75 mm x3.55mm) and furnishing with moulded timber beading of size 25mmx15mm around the panels complete as per drawing (moulded timber bead and all fittings except hinges to be paid separately). b) With 1st class local wood (Hollock / Bola/ Bonsum) (iii) 30 mm thick with panel inserts of 20mm thickness.	4.20	Sqm		
11	Providing antiskid Tiles of approved quality size, shape and thickness not less than 8mm on floor, skirting over a cement mortar bed of 15mm thick in prop(1:3) approved make fix with fix-A-Tile complete at all levels specified and directed	5.00	Sqm		
12	Providing polished ceramic wall tiles of approved quality, size, shape and thickness not less than 8mm on walls and skirtings over cement mortar bed 10 mm thick in prop. 1:3 (1 cement : 3 coarse sand ) including cutting where necessary finished with flush pointing with Fix-A-Tile (Choksey / Sika / Pedelite / Rouf) /white cement slurry mixed with approved pigment to match shade of tiles complete at all levels as specified and directed. (Cement plastering to be measured and paid separately). (Coloured pigment should be in conformity with colour of tiles and as approved and directed by the Department). (Walls means both interior and exterior walls).	16.40	Sqm		
14	a) Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.	637.96	Sqm		
	<b>For CEILING</b>	144.63	Sqm		
	b) Extra over item no (a) above for removing dry or oil bound distemper on ceiling and in sloping roof.	144.63	Sqm		
	c) Applying one coat of distemper primer of approved brand and manufacture on wall surface after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and including preparing the surface even and sand papered	637.96	Sqm		

	smooth.				
15	For CEILING	144.63	Sqm		
	e) Extra over item no. (c) and (d) above for applying one coat of distemper primer/alkali resistant primer over ceiling and on sloping roof.	144.63	Sqm		
16	h). Distemping with dry distemper of approved brand and manufacture(one coat) and of required shade on old wall surface to give an even shade,after throughly brushing the surface clean of all grease, dirt, loose pieces of scales including preparing surface even and sand papered smooth.	637.96	Sqm		
	For CEILING	144.63	Sqm		
	l) Extra over item no. (h) above for distemping with dry distemper on ceiling and or sloping roof.	144.63	Sqm		
18	Applying priming coat over new wood and wood based surfaces over 100mm in girth/width after and including preparing the surface by throughly cleaning oil, grease, dirt and other foreign matter , sand papering and knotting	10.43	Sqm		
19	Painting one coat (excluding priming coat) on old wood and wood based surfaces with enamel paint to give an even shade including cleaning the surface of all dirt, dust and other foreign matter sand papering and stopping. <b>(i).Surfaces over 100mm in width or girth.</b> a). General purpose (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac).	174.56	Sqm		
20	Painting two coats on new G.C.I sheets with ready mixed anticorrosive paint of approved brand and shade suitable for painting over G.C.I sheets to give an even shade including the cleaning the rust patches with emery paper, dust ,dirt, grease and other foreign matter with water complete.	209.45	Sqm		
21	Providing plinth protection with bricks laid on edge and grouted with cement mortar 1:4 and finishing with cement pointing in prop. 1:1 complete.	107.59	Sqm		
22	Providing drain with brick work in cement mortar in proportion 1:5 with half brick thick side walls and 100mm thick C.C (1:3:6) base over one brick flat soling including 15mm thick cement plastering in prop. 1:3 finished with a floating coat of cement slurry as directed with necessary shuttering for sides and earth work in excavation of foundation trenches and refilling the sides after completion of work etc. <i>as specified</i> ii). 300mm wide and average 250mm deep with bed slope 1 in 150 with initial depth of 100mm.	76.85	RM		

23	Supplying, fitting and fixing ceiling tiles of 10mm thick made from Duratuff medium density fibre board in size 1200mm x 1200mm x 10mm with Sal wood timber frame (to be measured and paid separately) leaving an expansion gap of 3mm with necessary nails, screws etc. including 1st class local wood (Hollock /Bonsum / Sundi etc.) beading of size 50mm x 12mm complete as directed and specified.	26.95	Sqm		
24	Providing fitting and fixing white vitreous china pedestal type water closet (European type W.C pan 400mm high ) of Parryware/Hindware make with seat and lead ,CP brass hinges and rubber buffers ,10 litre low level PVC flushing cistern with fittings, CI/MS brackets , 40 mm dia flush band with fittings including painting of fittings and brackets, required. A) Parryare make (a) White (ii) Universal closet P trap (Cat no C0272)( Inclusive of seat cover)	1	Each		
25	Supplying fitting and fixing Chrome plated wall mixer complete as directed (I) Sona make A) wall mixer non telephonic	1	Each		
26	Supplying fitting and fixing PVC flushing cistern with all internal fittings with CI brackets including fitting and fixing standard size CP flush pipe, union clamps etc. complete as directed and specified (Pipes will be measured separately) I) Parryware make a) White i) Economy Single flush (Cat no C8090/C8055)	1	Each		
27	Providing fitting & fixing mirror with plastic frame of size 500 x 400 mm.....	2	Each		
28	Providing fitting & fixing C.P scaptray/soap dish complete as directed... (i) Jaquar make (a) Continental .....	1	Each		
29	Providing fixing C.P towel rail complete as directed.. (b) Sona make (i) diplomate 300 mm.....	1	Each		
30	Supplying fixing PVC pipes of 6 kg/m <sup>2</sup> 9Supreme/Prince) or other I.S.I approved..... (a) In exposed or in trenches. (ii) 110 mm dia..	7.00	Rm.		
	vent pipe.. PVC pipe 75mm dia.	8.00	Rm.		
31	Wirring for 5/6 pin 16 amps power plug point with 4 sq. mm PVC insulated..... 3.3.2) medium point up to 6m length	10	Each		

32	<p>Wiring for light/ fan/ call bell point with 2x1.5 sq mm P.V.C. insulated single core unsheathed industrial (Multistrand) cable FR conforming to IS-694: 1990 with flexible bright annealed electrolytic copper conductor for voltage grade up to 1100 volts (Finolex /RR Kabel /Nicco / Anchor or Equivalent Make as approved by the Deptt.) with flat 19 mm ISI marked casing 'n' capping (AKG / Precision/ Presto Plast/Polycab/ MW or equivalent make as approved by the Deptt.) in surface system, including 6 Amp flush type switch/ bell push (Anchor Penta/Gold medal /Kolor kany.Kom/ Havells or equivalent make as approved by the Deptt.) GI/ MS switch board (ISI marked) half conceal on wall with phenolic laminated sheet cover ,ceiling rose (Anchor/Gold medal /Kolor kany.Kom / Havells or equivalent make as approved by the Deptt.) etc. complete as directed and specified by the Deptt.</p> <p>1.1.1.) Short point up to 3.00 metre. length.</p> <p>1.1.2.) Medium point up to 6.00 metre. Length.</p>	10	Each		
33	<p>Supplying with fitting &amp; fixing T-5 luminaries complete with all accessories such as ballast, starter, lamp etc directly on wall/ceilling including connection cable as directed by the Deptt. with 1.5 sqm. PVC insulated S.C. copper conductor as required as directed by the Deptt.</p>	10	Each		
<b>Total (Including GST)</b>					

Bidder seal & sign