

PRICE BID

Name of Work: Urgent repairing of damaged rusted tower legs at 9 (Nine) locations (172, 161,158, 157,122,121,73,65,09) and repairing of damaged beam at 2(Two) locations (192 & 95) of 132 KV North-Lakhimpur-Dhemaji S/C transmission line.

Sl no	Description of Items	Unit	Qty	Rate (inclusive of all taxes)	Amount
1.0	Repairing of Leg : 4 Legs Earth work in foundation pits including shoring, shuttering and necessary dewatering, refilling of earth work after completion of foundation work, demolishing of PCC/RCC chimney of foundation of upto a depth of below the tie beam, fabrication of cut pieces stubs, cleats, butt jointing, head loading etc to the site, PCC/RCC works in foundation & tie beam in proportion 1:2:4 with maximum size of aggregate 38 mm for PCC and 20 mm for RCC including cost of materials, labour, cement, rod,equipments etc. complete as directed by field officer. Total tower 1 No x 4 Legs= 4 Legs	Legs	4		
2.0	Repairing of Beam : 4 Beams Earth work including shoring, shuttering and necessary dewatering, breaking of PCC/RCC of damaged tie beam head loading of construction materials etc to the site, PCC/RCC works in tie beam in proportion 1:2:4 with maximum size of aggregate 38 mm for PCC and 20 mm for RCC including cost of materials, labour, cement, rod,equipments etc. complete as directed by field officer. Total tower 1 No x 4 Beams= 4 Beams	Beams	4		
Total amount for repairing of legs of 9 no. towers -Rs.					
Total amount for repairing of beams of 2 no. towers -Rs.					
Grand Total Rs.					